

AMENDMENT 1 TO COVER FUEL TRUCK STORAGE BUILDING

Attachment A Section "Site Work" paragraph 8: Delete 120'-0 x 120'-0 replace with 235'-0 x 60'-0.

Attachment A Section "Site Work" paragraph 9: Delete 80'-0 replace with 200'-0.

Attachment A Section "Site Work" paragraph 10: Delete 80'-0 replace with 200'-0.

Attachment A Section "Site Work" paragraph 12: Delete the second sentence; Replace with "Bollards will be located, two at the exterior of each overhead door jamb on the entrance side of the building, for a total of eighteen (18)."

Attachment A Section "Site Work": Insert new paragraph paragraph 13a: "Provide, place, backfill and compact 12" crushed stone sub-base under the 30' wide concrete aprons around each of the 235' long sides of the building."

Attachment A Section "Site Work" paragraph 19: Delete 2 ½" replace with 3½".

Attachment A Section "Concrete" paragraph 8: Delete 80'-0 replace with 200'-0.

Attachment A Section "Concrete": Insert new paragraph 10a: "Form, reinforce, place and finish, concrete slab for a 30' wide concrete aprons around each of the 235' long sides of the building. Pad to be 8" thick and reinforced with #4 reinforcing steel. Concrete to be 4500 psi. with a broom finish."

Attachment A Section "Metals" paragraph 1: Delete (12) replace with (18).

Attachment A Section "Metals" paragraph 2: Delete 80'-0 replace with 200'-0.

Attachment A Section "Doors, Windows & Glass" paragraph 1: Delete four (4) replace with six (6).

Attachment A Section "Doors, Windows & Glass" paragraph 2: Delete (2) replace with (18).

Attachment A Section "Doors, Windows & Glass" paragraph 2: Delete 20'-0 replace with 15'-0.

Attachment A Section "Finishes" paragraph 2b: Delete 4 replace with 6.

Attachment A Section "Finishes" paragraph 2c: Delete 8 replace with 18.

Attachment A Section "Finishes" paragraph 2e: Delete (2) replace with (18).

Attachment A Section "Finishes" paragraph 2e: Delete 20' replace with 15'.

Attachment A Section "Special Construction" 1st sentence: Delete 120'-0 wide (span) x 120'-0 replace with 60'-0 wide (span) x 235'-0.

Attachment A Section "Special Construction" paragraph 2: Delete 120'-0 replace with 60'-0 in both locations.

Attachment A Section "Special Construction" paragraph 3: Delete paragraph and replace with "Building length to be 235'-0 long with nine (9) column bays at 25'-0 spacing. Building dimension length to be 235'-0 to outside face of concrete foundation."

Attachment A Section "Special Construction" paragraph 8: Delete 20'-0 replace with 15'-0.

Attachment A Section "Special Construction" paragraph 9: Delete (4) replace with (6).

Attachment A Section "Fire Suppression" paragraph 6: Delete eight (8) replace with nine (9).

Attachment A Section "Fire Suppression" : Add paragraph 9, "Provide two (2) 2 hr rated fire stop walls to be placed between every three (3) column bays."

Attachment A Section "Mechanical" paragraph 4: Delete 1st sentence replace with "Provide and install exhaust fans, one (1) located at each gable end of the building, and one (1) on the 235' side of the building."

Attachment A Section "Mechanical" paragraph 4; sentence 3: Delete both replace with three.

Attachment A Section "Mechanical" paragraph 4: Delete sentence 4.

Attachment A Section "Mechanical" paragraph 5, sentence 1: Delete two (2) replace with three (3).

Attachment A Section "Electrical" paragraph 2, sentence 1: Delete "each building" replace with "the building."

Attachment A Section "Electrical" : Delete paragraph 3 replace with "Provide and install power supply wiring to three (3) exhaust fans one at each gable end of building and one on the 235' long side."

Attachment A Section "Electrical" paragraph 5: Delete (2) replace with (18).

Attachment A Section "Electrical": Delete paragraph 6 replace with "Provide and install outlets for trucks at outer walls, 1 at each bay along one of the 235' long sides between the garage doors."

Attachment A Section "Electrical" paragraph 12; Delete last sentence.

Attachment B "Military Construction Form (DD Form 1391): Delete in its entirety replace with the attached Military Construction Form (DD Form 1391).


