

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT				1. CONTRACT ID CODE J		PAGE OF PAGES 1 24	
2. AMENDMENT/MODIFICATION NO. 0005		3. EFFECTIVE DATE 15-Apr-2005		4. REQUISITION/PURCHASE REQ. NO. W16ROE-5006-7751		5. PROJECT NO.(If applicable)	
6. ISSUED BY USA ENGINEER DISTRICT, NEW YORK ATTN:CENAN-CT ROOM 1843 26 FEDERAL PLAZA NEW YORK NY 10278		CODE W912DS		7. ADMINISTERED BY (If other than item 6) See Item 6		CODE	
8. NAME AND ADDRESS OF CONTRACTOR (No., Street, County, State and Zip Code)				X		9A. AMENDMENT OF SOLICITATION NO. W912DS-05-B-0007	
				X		9B. DATED (SEE ITEM 11) 11-Mar-2005	
						10A. MOD. OF CONTRACT/ORDER NO.	
						10B. DATED (SEE ITEM 13)	
CODE		FACILITY CODE					
11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS							
<input checked="" type="checkbox"/> The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offer <input checked="" type="checkbox"/> is extended, <input type="checkbox"/> is not extended. Offer must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended by one of the following methods: (a) By completing Items 8 and 15, and returning <u>1</u> copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.							
12. ACCOUNTING AND APPROPRIATION DATA (If required)							
13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.							
A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.							
B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(B).							
C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:							
D. OTHER (Specify type of modification and authority)							
E. IMPORTANT: Contractor <input type="checkbox"/> is not, <input type="checkbox"/> is required to sign this document and return _____ copies to the issuing office.							
14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.) The purpose of this amendment 0005 to solicitation W912DS-05-B-0007 is to implement the attached specification changes. As a result of this amendment, the bid opening date and time is changed as follows: FROM: 19 April 2005 @ 2:00 PM TO: 21 April 2005 @ 2:00 PM Additionally, a cutoff date for written questions and RFI's is established as 19 April 2005 @ 12:00 noon. ALL OTHER TERMS AND CONDITIONS REMAIN IN FULL FORCE AND EFFECT. Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.							
15A. NAME AND TITLE OF SIGNER (Type or print)				16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)			
				TEL: _____ EMAIL: _____			
15B. CONTRACTOR/OFFEROR _____ (Signature of person authorized to sign)		15C. DATE SIGNED		16B. UNITED STATES OF AMERICA BY _____ (Signature of Contracting Officer)		16C. DATE SIGNED 15-Apr-2005	

SECTION SF 30 BLOCK 14 CONTINUATION PAGE

SUMMARY OF CHANGES

SECTION 00010 - SOLICITATION CONTRACT FORM

The required response date/time has changed from 19-Apr-2005 02:00 PM to 21-Apr-2005 02:00 PM.

SECTION 00100 - BIDDING SCHEDULE/INSTRUCTIONS TO BIDDERS

The following have been added by full text:

AMENDMENT 0005 CHANGES**NOTICE TO BIDDERS**

Failure of the bidder to
Acknowledge receipt of
this Amendment in
Item 19 of Standard Form
1442 (Pg. 00010-2) may
result in REJECTION of
the bid.

IFB NO. W912DS-05-B-0007

Amendment No. 5

Department of the Army, NYD
Corps of Engineers
New York, NY 10278-0090

**AMENDMENT NO. 5 TO SPECIFICATIONS ISSUED 11 MARCH 2005 FOR
COVERED DEPARTURE/ARRIVAL FACILITY, FORT DRUM, NEW YORK**

TO BIDDER**1. Make the Following Changes in the Specifications.****SECTION 05500 – MISCELLANEOUS METAL**

Delete Article “2.2 CORNER GUARDS AND SHIELDS” in its entirety.

SECTION 09100 – METAL SUPPORT ASSEMBLIES

Delete Section 09100, pages 1 thru 4, in its entirety.

SECTION 09250 – GYPSUM BOARD

Delete Section 09250, pages 1 thru 7, in its entirety.

SECTION 13930 - WET PIPE SPRINKLER SYSTEM, FIRE PROTECTION

Article “1.2 GENERAL REQUIREMENTS”

In subparagraph 1.2.1.2, change the first 2 sentences to read:

The design of the system shall be based upon a water supply with a flow of 6,260 L/min at a residual pressure of 517 kPa and a flow of 7,383 L/min at a residual pressure of 317 kPa. Water supply shall be presumed available at the base of the riser. Hydraulic calculations shall be . . .

SECTION 13935 - DRY PIPE SPRINKLER SYSTEM, FIRE PROTECTION

Article "1.2 GENERAL REQUIREMENTS"

In subparagraph 1.2.1.2, change the first 2 sentences to read:

The design of the system shall be based upon a water supply with a flow of 7,270 L/min at a residual pressure of 531 kPa and a flow of 8,708 L/min at a residual pressure of 338 kPa. Water supply shall be presumed available at the base of the riser. Hydraulic calculations shall be . . .

SECTION 13930 - WET PIPE SPRINKLER SYSTEM, FIRE PROTECTION

Delete Section 13930, pages 1 thru 20, in its entirety and insert the following pages 1 thru 20, all Rev. 1, in its place.

"SECTION TABLE OF CONTENTS

DIVISION 13 - SPECIAL CONSTRUCTION

SECTION 13930

WET PIPE SPRINKLER SYSTEM, FIRE PROTECTION

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 GENERAL REQUIREMENTS
 - 1.2.1 Hydraulic Design
 - 1.2.1.1 Hose Demand
 - 1.2.1.2 Basis for Calculations
 - 1.2.2 Sprinkler Coverage
- 1.3 COORDINATION OF TRADES
- 1.4 DELIVERY AND STORAGE
- 1.5 FIELD MEASUREMENTS
- 1.6 SUBMITTALS
- 1.7 HYDRAULIC CALCULATIONS
- 1.8 FIRE PROTECTION SPECIALIST
- 1.9 SPRINKLER SYSTEM INSTALLER
- 1.10 REGULATORY REQUIREMENTS
- 1.11 SPARE PARTS
- 1.12 SHOP DRAWINGS

PART 2 PRODUCTS

- 2.1 STANDARD PRODUCTS
- 2.2 NAMEPLATES
- 2.3 REQUIREMENTS FOR FIRE PROTECTION SERVICE
- 2.4 UNDERGROUND PIPING COMPONENTS
 - 2.4.1 Pipe
 - 2.4.2 Fittings and Gaskets
 - 2.4.3 Gate Valve and Indicator Posts
- 2.5 ABOVEGROUND PIPING COMPONENTS
 - 2.5.1 Steel Piping Components
 - 2.5.1.1 Steel Pipe
 - 2.5.1.2 Fittings for Non-Grooved Steel Pipe
 - 2.5.1.3 Grooved Mechanical Joints and Fittings
 - 2.5.1.4 Flanges
 - 2.5.1.5 Bolts, Nut, and Washers
 - 2.5.2 Pipe Hangers
 - 2.5.3 Valves
 - 2.5.3.1 Control Valve and Gate Valve
 - 2.5.3.2 Check Valve
- 2.6 ALARM CHECK VALVE ASSEMBLY
- 2.7 ALARM INITIATING AND SUPERVISORY DEVICES
 - 2.7.1 Sprinkler Waterflow Indicator Switch, Vane Type
 - 2.7.2 Sprinkler Pressure (Waterflow) Alarm Switch
 - 2.7.3 Valve Supervisory (Tamper) Switch
- 2.8 SPRINKLERS
 - 2.8.1 Pendent Sprinkler
 - 2.8.2 Upright Sprinkler
 - 2.8.3 Sidewall Sprinkler

- 2.8.4 Dry Sprinkler Assembly
- 2.9 DISINFECTING MATERIALS
 - 2.9.1 Liquid Chlorine
 - 2.9.2 Hypochlorites
- 2.10 ACCESSORIES
 - 2.10.1 Sprinkler Cabinet
 - 2.10.2 Pendent Sprinkler Escutcheon
 - 2.10.3 Pipe Escutcheon
 - 2.10.4 Sprinkler Guard
 - 2.10.5 Identification Sign

PART 3 EXECUTION

- 3.1 FIRE PROTECTION RELATED SUBMITTALS
- 3.2 INSTALLATION REQUIREMENTS
- 3.3 INSPECTION BY FIRE PROTECTION SPECIALIST
- 3.4 ABOVEGROUND PIPING INSTALLATION
 - 3.4.1 Protection of Piping Against Earthquake Damage
 - 3.4.2 Piping in Exposed Areas
 - 3.4.3 Piping in Finished Areas
 - 3.4.4 Pendent Sprinklers
 - 3.4.4.1 Pendent Sprinkler Locations
 - 3.4.5 Upright Sprinklers
 - 3.4.6 Pipe Joints
 - 3.4.7 Reducers
 - 3.4.8 Pipe Penetrations
 - 3.4.9 Escutcheons
 - 3.4.10 Inspector's Test Connection
 - 3.4.11 Drains
 - 3.4.12 Identification Signs
- 3.5 UNDERGROUND PIPING INSTALLATION
- 3.6 EARTHWORK
- 3.7 ELECTRICAL WORK
- 3.8 PIPE COLOR CODE MARKING
- 3.9 PRELIMINARY TESTS
 - 3.9.1 Underground Piping
 - 3.9.1.1 Flushing
 - 3.9.1.2 Hydrostatic Testing
 - 3.9.2 Aboveground Piping
 - 3.9.2.1 Hydrostatic Testing
 - 3.9.3 Testing of Alarm Devices
 - 3.9.4 Main Drain Flow Test
- 3.10 FINAL ACCEPTANCE TEST
- 3.11 ON-SITE TRAINING

-- End of Section Table of Contents --

SECTION 13930

WET PIPE SPRINKLER SYSTEM, FIRE PROTECTION

PART 1 GENERAL1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN WATER WORKS ASSOCIATION (AWWA)

AWWA B300	(1999) Hypochlorites
AWWA B301	(1999) Liquid Chlorine
AWWA C104	(1995) Cement-Mortar Lining for Ductile-Iron Pipe and Fittings for Water
AWWA C110	(1998) Ductile-Iron and Gray-Iron Fittings, 3 In. Through 48 In. (76 mm through 1219 mm), for Water
AWWA C111	(2000) Rubber-Gasket Joints for Ductile-Iron Pressure Pipe and Fittings
AWWA C151	(2002) Ductile-Iron Pipe, Centrifugally Cast, for Water
AWWA C203	(2002; A C203a-99) Coal-Tar Protective Coatings and Linings for Steel Water Pipelines - Enamel and Tape - Hot-Applied

ASME INTERNATIONAL (ASME)

ASME B16.1	(1998) Cast Iron Pipe Flanges and Flanged Fittings
ASME B16.11	(2002) Forged Fittings, Socket-Welding and Threaded
ASME B16.21	(1992) Nonmetallic Flat Gaskets for Pipe Flanges
ASME B16.3	(1998) Malleable Iron Threaded Fittings
ASME B16.4	(1998) Gray Iron Threaded Fittings
ASME B16.9	(2001) Factory-Made Wrought Steel Buttwelding Fittings

ASME B18.2.1 (1996) Square and Hex Bolts and Screws, Inch Series

ASME B18.2.2 (1987; R 1999) Square and Hex Nuts

ASTM INTERNATIONAL (ASTM)

ASTM A 135 (2001) Electric-Resistance-Welded Steel Pipe

ASTM A 183 (2003) Carbon Steel Track Bolts and Nuts

ASTM A 193/A 193M (2003) Alloy-Steel and Stainless Steel Bolting Materials for High-Temperature Service

ASTM A 449 (2000) Quenched and Tempered Steel Bolts and Studs

ASTM A 47/A 47M (1999) Ferritic Malleable Iron Castings

ASTM A 53/A 53M (2002) Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless

ASTM A 536 (1984; R 1999e1) Ductile Iron Castings

ASTM A 563M (2001) Carbon and Alloy Steel Nuts (Metric)

ASTM A 795 (2000) Black and Hot-Dipped Zinc-Coated (Galvanized) Welded and Seamless Steel Pipe for Fire Protection Use

ASTM F 436M (2003) Hardened Steel Washers (Metric)

FM GLOBAL (FM)

FM P7825a (2003) Approval Guide Fire Protection

FM P7825b (2003) Approval Guide Electrical Equipment

MANUFACTURERS STANDARDIZATION SOCIETY OF THE VALVE AND FITTINGS INDUSTRY (MSS)

MSS SP-71 (1997) Gray Iron Swing Check Valves, Flanged and Threaded Ends

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 101 (2003) Life Safety Code

NFPA 13 (2002) Installation of Sprinkler Systems

NFPA 13D (2002) Installation of Sprinkler Systems in One- and Two-Family Dwellings and Manufactured Homes

NFPA 13R (2002) Installation of Sprinkler Systems in Residential Occupancies Up to and Including Four Stories in Height

NFPA 24 (2002) Installation of Private Fire Service Mains and Their Appurtenances

NATIONAL INSTITUTE FOR CERTIFICATION IN ENGINEERING TECHNOLOGIES
(NICET)

NICET 1014-7 (1995) Program Detail Manual for Certification in the Field of Fire Protection Engineering Technology (Field Code 003) Subfield of Automatic Sprinkler System Layout

UNDERWRITERS LABORATORIES (UL)

UL Bld Mat Dir (2003) Building Materials Directory

UL Fire Prot Dir (2003) Fire Protection Equipment Directory

1.2 GENERAL REQUIREMENTS

Wet pipe sprinkler system shall be provided in all areas of the D/AACG Building Addition. The sprinkler system shall provide fire sprinkler protection for the entire area. Except as modified herein, the system shall be designed and installed in accordance with NFPA 13. Rack sprinklers shall be in accordance with NFPA 13. Pipe sizes, which are not indicated on drawings, shall be determined by hydraulic calculation. The Contractor shall design any portions of the sprinkler system that are not indicated on the drawings including locating sprinklers, piping and equipment, and size piping and equipment when this information is not indicated on the drawings or is not specified herein. The design of the sprinkler system shall be based on hydraulic calculations, and the other provisions specified herein.

1.2.1 Hydraulic Design

The system shall be hydraulically designed to discharge a minimum density of 12.2 L/min per square meter over the hydraulically most demanding 280 square meters of floor area. The minimum pipe size for branch lines in gridded systems shall be 32 mm. Hydraulic calculations shall be in accordance with the Area/Density Method of NFPA 13. Water velocity in the piping shall not exceed 6 m/s.

1.2.1.1 Hose Demand

An allowance for exterior hose streams of 2,850 L/min shall be added to the sprinkler system demand at the fire hydrant shown on the drawings closest to the point where the water service enters the building.

1.2.1.2 Basis for Calculations

The design of the system shall be based upon a water supply with a static pressure of 744.6 kPa, and a flow of 6,260 L/min at a residual pressure of 517 kPa. Water supply shall be presumed available at the point of connection to existing. Hydraulic calculations shall be based upon the Hazen-Williams formula with a "C" value of 120 for steel

piping, 150 for copper tubing, 140 for new cement-lined ductile-iron piping, and 100 for existing underground piping.

1.2.2 Sprinkler Coverage

Sprinklers shall be uniformly spaced on branch lines. In buildings protected by automatic sprinklers, sprinklers shall provide coverage throughout 100 percent of the building. This includes, but is not limited to, telephone rooms, electrical equipment rooms, boiler rooms, switchgear rooms, transformer rooms, and other electrical and mechanical spaces. Coverage per sprinkler shall be in accordance with NFPA 13, but shall not exceed 9 square m for extra hazard occupancies and storage areas, 12 square m for ordinary hazard occupancies, and 21 square m for light hazard occupancies. Exceptions are as follows:

- 1) Facilities that are designed in accordance with NFPA 13R and NFPA 13D.
- 2) Sprinklers may be omitted from small rooms, which are exempted for specific occupancies in accordance with NFPA 101.

1.3 COORDINATION OF TRADES

Piping offsets, fittings, and any other accessories required shall be furnished as required to provide a complete installation and to eliminate interference with other construction. Sprinkler shall be installed over and under ducts, piping and platforms when such equipment can negatively effect or disrupt the sprinkler discharge pattern and coverage.

1.4 DELIVERY AND STORAGE

All equipment delivered and placed in storage shall be housed in a manner to preclude any damage from the weather, humidity and temperature variations, dirt and dust, or other contaminants. Additionally, all pipes shall either be capped or plugged until installed.

1.5 FIELD MEASUREMENTS

The Contractor shall become familiar with all details of the work, verify all dimensions in the field, and shall advise the Contracting Officer of any discrepancy before performing the work.

1.6 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Shop Drawings; G, RO

Three copies of the Sprinkler System Shop Drawings, no later than 21 days prior to the start of sprinkler system installation. Shop

Drawings shall be signed and sealed by the fire protection specialist.

As-Built Drawings

As-built shop drawings, at least 14 days after completion of the Final Tests. The Sprinkler System Drawings shall be updated to reflect as-built conditions after all related work is completed and shall be on reproducible full-size Mylar film. As-Built Shop Drawings shall be signed and sealed by the fire protection specialist.

SD-03 Product Data

Fire Protection Related Submittals

A list of the Fire Protection Related Submittals, no later than 7 days after the approval of the Fire Protection Specialist.

Sway Bracing; G, RO

For systems that are required to be protected against damage from earthquakes, load calculations shall be provided for sizing of sway bracing.

Materials and Equipment; G, RO

Manufacturer's catalog data included with the Sprinkler System Drawings for all items specified herein. The data shall be highlighted to show model, size, options, etc., that are intended for consideration. Data shall be adequate to demonstrate compliance with all contract requirements. In addition, a complete equipment list that includes equipment description, model number and quantity shall be provided.

Hydraulic Calculations; G, RO

Hydraulic calculations, including a drawing showing hydraulic reference points and pipe segments.

Spare Parts

Spare parts data shall be included for each different item of material and equipment specified.

Preliminary Tests; G, RO

Proposed procedures for Preliminary Tests, no later than 14 days prior to the proposed start of the tests. Proposed date and time to begin the preliminary tests.

Final Acceptance Test; G, RO

Proposed procedures for Final Acceptance Test, no later than 14 days prior to the proposed start of the tests. Proposed date and time to begin Final Acceptance Test, submitted with the Final

Acceptance Test Procedures. Notification shall be provided at least 14 days prior to the proposed start of the test. Notification shall include a copy of the Contractor's Material & Test Certificates.

On-site Training; G, RO

Proposed On-site Training schedule, at least 14 days prior to the start of related training.

Fire Protection Specialist; G, RO

The name and documentation of certification of the proposed Fire Protection Specialists, no later than 14 days after the Notice to Proceed and prior to the submittal of the sprinkler system drawings and hydraulic calculations.

Sprinkler System Installer; G, RO

The name and documentation of certification of the proposed Sprinkler System Installer, concurrent with submittal of the Fire Protection Specialist Qualifications.

SD-06 Test Reports

Preliminary Test Report; G, RO

Three copies of the completed Preliminary Test Report, no later than 7 days after the completion of the Preliminary Tests. The Preliminary Tests Report shall include both the Contractor's Material and Test Certificate for Underground Piping and the Contractor's Material and Test Certificate for Aboveground Piping. The Fire Protection Specialist shall sign all items in the Preliminary Tests Report.

Final Acceptance Test Report; G, RO

Three copies of the completed Final Acceptance Tests Reports, no later than 7 days after the completion of the Final Acceptance Tests. The Fire Protection Specialist shall sign all items in the Final Acceptance Report.

SD-07 Certificates

Inspection by Fire Protection Specialist; G, RO

Concurrent with the Final Acceptance Test Report, certification by the Fire Protection Specialist that the sprinkler system is installed in accordance with the contract requirements, including signed approval of the Preliminary and Final Acceptance Test Reports.

SD-10 Operation and Maintenance Data

Operating and Maintenance Instructions

Six manuals listing step-by-step procedures required for system startup, operation, shutdown, and routine maintenance, at least 14 days prior to field training. The manuals shall include the manufacturer's name, model number, parts list, list of parts and tools that should be kept in stock by the owner for routine maintenance including the name of a local supplier, simplified wiring and controls diagrams, troubleshooting guide, and recommended service organization (including address and telephone number) for each item of equipment. Each service organization submitted shall be capable of providing 4-hour on-site response to a service call on an emergency basis.

1.7 HYDRAULIC CALCULATIONS

Hydraulic calculations shall be as outlined in NFPA 13 except that calculations shall be performed by computer using software intended specifically for fire protection system design using the design data shown on the drawings. Software that uses k-factors for typical branch lines is not acceptable. Calculations shall be based on the water supply data shown on the drawings. Calculations shall substantiate that the design area used in the calculations is the most demanding hydraulically. Water supply curves and system requirements shall be plotted on semi-logarithmic graph paper so as to present a summary of the complete hydraulic calculation. A summary sheet listing sprinklers in the design area and their respective hydraulic reference points, elevations, actual discharge pressures and actual flows shall be provided. Elevations of hydraulic reference points (nodes) shall be indicated. Documentation shall identify each pipe individually and the nodes connected thereto. The diameter, length, flow, velocity, friction loss, number and type fittings, total friction loss in the pipe, equivalent pipe length and Hazen-Williams coefficient shall be indicated for each pipe. For gridded systems, calculations shall show peaking of demand area friction loss to verify that the hydraulically most demanding area is being used. Also for gridded systems, a flow diagram indicating the quantity and direction of flows shall be included. A drawing showing hydraulic reference points (nodes) and pipe designations used in the calculations shall be included and shall be independent of shop drawings.

1.8 FIRE PROTECTION SPECIALIST

Work specified in this section shall be performed under the supervision of and certified by the Fire Protection Specialist. The Fire Protection Specialist shall be an individual who is a registered professional engineer and a Full Member of the Society of Fire Protection Engineers or who is certified as a Level III Technician by National Institute for Certification in Engineering Technologies (NICET) in the Automatic Sprinkler System Layout subfield of Fire Protection Engineering Technology in accordance with NICET 1014-7. The Fire Protection Specialist shall be regularly engaged in the design and installation of the type and complexity of system specified in the Contract documents, and shall have served in a similar capacity for at least three systems that have performed in the manner intended for a period of not less than 6 months.

1.9 SPRINKLER SYSTEM INSTALLER

The Sprinkler System Installer shall perform work specified in this section. The Sprinkler System Installer shall be regularly engaged in the installation of the type and complexity of system specified in the Contract documents, and shall have served in a similar capacity for at least three systems that have performed in the manner intended for a period of not less than 6 months.

1.10 REGULATORY REQUIREMENTS

Compliance with referenced NFPA standards is mandatory. This includes advisory provisions listed in the appendices of such standards, as though the word "shall" had been substituted for the word "should" wherever it appears. In the event of a conflict between specific provisions of this specification and applicable NFPA standards, this specification shall govern. Reference to "authority having jurisdiction" shall be interpreted to mean the Contracting Officer.

1.11 SPARE PARTS

The Contractor shall submit spare parts data for each different item of material and equipment specified. The data shall include a complete list of parts and supplies, with current unit prices and source of supply, and a list of parts recommended by the manufacturer to be replaced after 1 year and 3 years of service. A list of special tools and test equipment required for maintenance and testing of the products supplied by the Contractor shall be included.

1.12 SHOP DRAWINGS

The Sprinkler System Shop Drawings shall conform to the requirements established for working plans as prescribed in NFPA 13. Drawings shall include plan and elevation views demonstrating that the equipment will fit the allotted spaces with clearance for installation and maintenance. Each set of drawings shall include the following:

- a. Descriptive index of drawings in the submittal with drawings listed in sequence by drawing number. A legend-identifying device symbols, nomenclature, and conventions used.
- b. Floor plans drawn to a scale not less than 1:100 which clearly show locations of sprinklers, risers, pipe hangers, seismic separation assemblies, sway bracing, inspector's test connections, drains, and other applicable details necessary to clearly describe the proposed arrangement. Each type of fitting used and the locations of bushings, reducing couplings, and welded joints shall be indicated.
- c. Actual center-to-center dimensions between sprinklers on branch lines and between branch lines; from end sprinklers to adjacent walls; from walls to branch lines; from sprinkler feed mains, cross-mains and branch lines to finished floor and roof or ceiling. A detail shall show the dimension from the sprinkler and sprinkler deflector to the ceiling in finished areas.

d. Longitudinal and transverse building sections showing typical branch line and cross-main pipe routing as well as elevation of each typical sprinkler above finished floor.

e. Details of each type of riser assembly; pipe hanger; sway bracing for earthquake protection, and restraint of underground water main at point-of-entry into the building, and electrical devices and interconnecting wiring.

PART 2 PRODUCTS

2.1 STANDARD PRODUCTS

Materials and equipment shall be standard products of a manufacturer regularly engaged in the manufacture of such products and shall essentially duplicate items that have been in satisfactory use for at least 2 years prior to bid opening.

2.2 NAMEPLATES

All equipment shall have a nameplate that identifies the manufacturer's name, address, type or style, model or serial number, and catalog number.

2.3 REQUIREMENTS FOR FIRE PROTECTION SERVICE

Materials and Equipment shall have been tested by Underwriters Laboratories, Inc. and listed in UL Fire Prot Dir or approved by Factory Mutual and listed in FM P7825a and FM P7825b. Where the terms "listed" or "approved" appear in this specification, such shall mean listed in UL Fire Prot Dir or FM P7825a and FM P7825b

2.4 UNDERGROUND PIPING COMPONENTS

2.4.1 Pipe

Piping from a point 150 mm above the floor to a point 1500 mm outside the building wall shall be ductile iron with a rated working pressure of 1034 kPa conforming to AWWA C151, with cement mortar lining conforming to AWWA C104. Piping more than 1500 mm outside the building walls shall comply with Section 02510 WATER DISTRIBUTION SYSTEM.

2.4.2 Fittings and Gaskets

Fittings shall be ductile iron conforming to AWWA C110. Gaskets shall be suitable in design and size for the pipe with which such gaskets are to be used. Gaskets for ductile iron pipe joints shall conform to AWWA C111.

2.4.3 Gate Valve and Indicator Posts

Gate valves for underground installation shall be of the inside screw type with counter-clockwise rotation to open. Where indicating type valves are shown or required, indicating valves shall be gate valves with an approved indicator post of a length to permit the top of the post to be located 900 mm above finished grade. Gate valves and indicator posts shall be listed in UL Fire Prot Dir or FM P7825a and FM P7825b.

2.5 ABOVEGROUND PIPING COMPONENTS

Aboveground piping shall be steel.

2.5.1 Steel Piping Components

2.5.1.1 Steel Pipe

Except as modified herein, steel pipe shall be black as permitted by NFPA 13 and shall conform to applicable provisions of ASTM A 795, ASTM A 53/A 53M, or ASTM A 135. Pipe in which threads or grooves are cut shall be Schedule 40 or shall be listed by Underwriters' Laboratories to have a corrosion resistance ratio (CRR) of 1.0 or greater after threads or grooves are cut. Pipe shall be marked with the name of the manufacturer, kind of pipe, and ASTM designation.

2.5.1.2 Fittings for Non-Grooved Steel Pipe

Fittings shall be cast iron conforming to ASME B16.4, steel conforming to ASME B16.9 or ASME B16.11, or malleable iron conforming to ASME B16.3. Steel press fittings shall be approved for fire protection systems. Galvanized fittings shall be used for piping systems or portions of piping systems utilizing galvanized piping. Fittings into which sprinklers drop nipples or riser nipples (sprigs) are screwed shall be threaded type. Plain-end fittings with mechanical couplings, fittings that use steel gripping devices to bite into the pipe and segmented welded fittings shall not be used.

2.5.1.3 Grooved Mechanical Joints and Fittings

Joints and fittings shall be designed for not less than 1200 kPa service and shall be the product of the same manufacturer; segmented welded fittings shall not be used. Fitting and coupling houses shall be malleable iron conforming to ASTM A 47/A 47M, Grade 32510; ductile iron conforming to ASTM A 536, Grade 65-45-12. Gasket shall be the flush type that fills the entire cavity between the fitting and the pipe. Nuts and bolts shall be heat-treated steel conforming to ASTM A 183 and shall be cadmium plated or zinc electroplated.

2.5.1.4 Flanges

Flanges shall conform to NFPA 13 and ASME B16.1. Gaskets shall be non-asbestos compressed material in accordance with ASME B16.21, 1.6 mm thick, and full face or self-centering flat ring type.

2.5.1.5 Bolts, Nut, and Washers

Bolts shall be squarehead conforming to ASME B18.2.1 or ASTM A 449, Type 1 or 2 and shall extend no less than three full threads beyond the nut with bolts tightened to the required torque. Nuts shall be hexagon type conforming to ASME B18.2.2 ASTM A 193/A 193M, Grade 5 or ASTM A 563M, Grade C3 DH3. Washers shall meet the requirements of ASTM F 436M. Flat circular washers shall be provided under all bolt heads and nuts.

2.5.2 Pipe Hangers

Hangers shall be listed in **UL Fire Prot Dir** or **FM P7825a** and **FM P7825b** and of the type suitable for the application, construction, and pipe type and sized to be supported.

2.5.3 Valves

2.5.3.1 Control Valve and Gate Valve

Manually operated sprinkler control valve and gate valve shall be outside stem and yoke (OS&Y) type and shall be listed in **UL Bld Mat Dir** or **FM P7825a** and **FM P7825b**.

2.5.3.2 Check Valve

Check valve 50 mm and larger shall be listed in **UL Bld Mat Dir** or **FM P7825a** and **FM P7825b**. Check valves 100 mm and larger shall be of the swing type with flanged cast iron body and flanged inspection plate, shall have a clear waterway and shall meet the requirements of **MSS SP-71**, for Type 3 or 4.

2.6 ALARM CHECK VALVE ASSEMBLY

Assembly shall include an alarm check valve, standard trim piping, pressure gauges, bypass, retarding chamber, testing valves, main drain, and other components as required for a fully operational system.

2.7 ALARM INITIATING AND SUPERVISORY DEVICES

2.7.1 Sprinkler Waterflow Indicator Switch, Vane Type

Switch shall be vane type with a pipe saddle and cast aluminum housing. The electro-mechanical device shall include a flexible, low-density polyethylene paddle conforming to the inside diameter of the fire protection pipe. The device shall sense water movements and be capable of detecting a sustained flow of 38 L/min or greater. The device shall contain a retard device adjustable from 0 to 90 seconds to reduce the possibility of false alarms caused by transient flow surges. The switch shall be tamper resistant and contain two SPDT (Form C) contacts arranged to transfer upon removal of the housing cover, and shall be equipped with a silicone rubber gasket to assure positive water seal and a dustproof cover and gasket to seal the mechanism from dirt and moisture.

2.7.2 Sprinkler Pressure (Waterflow) Alarm Switch

Pressure switch shall include a metal housing with a neoprene diaphragm, SPDT snap action switches and a 15 mm NPT male pipe thread. The switch shall have a maximum service pressure rating of 1207 kPa. There shall be two SPDT (Form C) contacts factory adjusted to operate at 28 to 55 kPa. The switch shall be capable of being mounted in any position in the alarm line trim piping of the alarm check valve.

2.7.3 Valve Supervisory (Tamper) Switch

Switch shall be suitable for mounting to the type of control valve to be supervised open. The switch shall be tamper resistant and contain one set of SPDT (Form C) contacts arranged to transfer upon removal of the housing cover or closure of the valve of more than two rotations of the valve stem.

2.8 SPRINKLERS

Sprinklers with internal O-rings shall not be used. Sprinklers shall be used in accordance with their listed coverage limitations. Temperature classification shall be intermediate. Sprinklers in high heat areas including attic spaces or in close proximity to unit heaters shall have temperature classification in accordance with **NFPA 13**. Extended coverage sprinklers shall not be used.

2.8.1 Pendent Sprinkler

Pendent sprinkler shall be of the fusible strut or glass bulb type, type with nominal 12.7 mm or 13.5 mm orifice. Pendent sprinklers shall have a polished chrome finish.

2.8.2 Upright Sprinkler

Upright sprinkler shall be brass and shall have a nominal 12.7 mm or 13.5 mm orifice.

2.8.3 Sidewall Sprinkler

Sidewall sprinkler shall have a nominal 12.7 mm orifice. Sidewall sprinkler shall have a brass finish. Sidewall sprinkler shall be the quick-response type.

2.8.4 Dry Sprinkler Assembly

Dry sprinkler assembly shall be of the pendent, upright, or sidewall, type. Assembly shall include an integral escutcheon. Maximum length shall not exceed maximum indicated in **UL Fire Prot Dir**. Sprinklers shall have a polished chrome finish.

2.9 DISINFECTING MATERIALS

2.9.1 Liquid Chlorine

Liquid chlorine shall conform to **AWWA B301**.

2.9.2 Hypochlorites

Calcium hypochlorite and sodium hypochlorite shall conform to **AWWA B300**.

2.10 ACCESSORIES

2.10.1 Sprinkler Cabinet

Spare sprinklers shall be provided in accordance with **NFPA 13** and shall be packed in a suitable metal or plastic cabinet. Spare sprinklers shall be representative of, and in proportion to, the number of each type and

temperature rating of the sprinklers installed. At least one wrench of each type required shall be provided.

2.10.2 Pendent Sprinkler Escutcheon

Escutcheon shall be one-piece metallic type with a depth of less than 20 mm and suitable for installation on pendent sprinklers. The escutcheon shall have a factory finish that matches the pendent sprinkler heads.

2.10.3 Pipe Escutcheon

Escutcheon shall be polished chromium-plated zinc alloy, or polished chromium-plated copper alloy. Escutcheons shall be either one-piece or split-pattern, held in place by internal spring tension or set screw.

2.10.4 Sprinkler Guard

Guard shall be a steel wire cage designed to encase the sprinkler and protect it from mechanical damage. Guards shall be provided on sprinklers located in all areas of the building.

2.10.5 Identification Sign

Valve identification sign shall be minimum 150 mm wide x 50 mm high with enamel baked finish on minimum 1.214 mm steel or 0.6 mm aluminum with red letters on a white background or white letters on red background. Wording of sign shall include, but not be limited to "main drain," "auxiliary drain," "inspector's test," "alarm test," "alarm line," and similar wording as required to identify operational components.

PART 3 EXECUTION

3.1 FIRE PROTECTION RELATED SUBMITTALS

The Fire Protection Specialist shall prepare a list of the submittals from the Contract Submittal Register that relate to the successful installation of the sprinkler systems(s). The submittals identified on this list shall be accompanied by a letter of approval signed and dated by the Fire Protection Specialist when submitted to the Government.

3.2 INSTALLATION REQUIREMENTS

The installation shall be in accordance with the applicable provisions of **NFPA 13**, **NFPA 24** and publications referenced therein. Installation of in-rack sprinklers shall comply with applicable provisions of **NFPA 13**.

3.3 INSPECTION BY FIRE PROTECTION SPECIALIST

The Fire Protection Specialist shall inspect the sprinkler system periodically during the installation to assure that the sprinkler system is being provided and installed in accordance with the contract requirements. The Fire Protection Specialist shall witness the preliminary and final tests, and shall sign the test results. The Fire Protection Specialist, after completion of the system inspections and a successful final test, shall certify in writing that the system has been installed in accordance

with the contract requirements. Any discrepancy shall be brought to the attention of the Contracting Officer in writing, no later than three working days after the discrepancy is discovered.

3.4 ABOVEGROUND PIPING INSTALLATION

3.4.1 Protection of Piping Against Earthquake Damage

The system piping shall be protected against damage from earthquakes. Seismic protection shall include flexible and rigid couplings, sway bracing, seismic separation assemblies where piping crosses building seismic separation joints, and other features as required by NFPA 13 for protection of piping against damage from earthquakes.

3.4.2 Piping in Exposed Areas

Exposed piping shall be installed so as not to diminish exit access widths, corridors or equipment access. Exposed horizontal piping, including drain piping, shall be installed to provide maximum headroom.

3.4.3 Piping in Finished Areas

In areas with suspended or dropped ceilings and in areas with concealed spaces above the ceiling, piping shall be concealed above ceilings. Piping shall be inspected, tested and approved before being concealed. Risers and similar vertical runs of piping in finished areas shall be concealed.

3.4.4 Pendent Sprinklers

Drop nipples to pendent sprinklers shall consist of minimum 25 mm pipe with a reducing coupling into which the sprinkler shall be threaded. Hangers shall be provided on arm-overs to drop nipples supplying pendent sprinklers when the arm-over exceeds 300 mm. Where sprinklers are installed below suspended or dropped ceilings, drop nipples shall be cut such that sprinkler ceiling plates or escutcheons are of a uniform depth throughout the finished space. The outlet of the reducing coupling shall not extend more than 25 mm below the underside of the ceiling. On pendent sprinklers installed below suspended or dropped ceilings, the distance from the sprinkler deflector to the underside of the ceiling shall not exceed 100 mm. Recessed pendent sprinklers shall be installed such that the distance from the sprinkler deflector to the underside of the ceiling shall not exceed the manufacturer's listed range and shall be of uniform depth throughout the finished area.

3.4.4.1 Pendent Sprinkler Locations

Pendent sprinklers in suspended ceilings shall be a minimum of 150 mm from ceiling grid.

3.4.5 Upright Sprinklers

Riser nipples or "sprigs" to upright sprinklers shall contain no fittings between the branch line tee and the reducing coupling at the sprinkler. Riser nipples exceeding 750 mm in length shall be individually supported.

3.4.6 Pipe Joints

Pipe joints shall conform to NFPA 13, except as modified herein. Not more than four threads shall show after joint is made up. Welded joints will be permitted, only if welding operations are performed as required by NFPA 13 at the Contractor's fabrication shop, not at the project construction site. Flanged joints shall be provided where indicated or required by NFPA 13. Grooved pipe and fittings shall be prepared in accordance with the manufacturer's latest published specification according to pipe material, wall thickness and size. Grooved couplings, fittings and grooving tools shall be products of the same manufacturer. For copper tubing, pipe and groove dimensions shall comply with the tolerances specified by the coupling manufacturer. The diameter of grooves made in the field shall be measured using a "go/no-go" gauge, vernier or dial caliper, narrow-land micrometer, or other method specifically approved by the coupling manufacturer for the intended application. Groove width and dimension of groove from end of pipe shall be measured and recorded for each change in grooving tool setup to verify compliance with coupling manufacturer's tolerances. Grooved joints shall not be used in concealed locations, such as behind solid walls or ceilings, unless an access panel is shown on the drawings for servicing or adjusting the joint.

3.4.7 Reducers

Reductions in pipe sizes shall be made with one-piece tapered reducing fittings. The use of grooved-end or rubber-gasketed reducing couplings will not be permitted. When standard fittings of the required size are not manufactured, single bushings of the face type will be permitted. Where used, face bushings shall be installed with the outer face flush with the face of the fitting opening being reduced. Bushings shall not be used in elbow fittings, in more than one outlet of a tee, in more than two outlets of a cross, or where the reduction in size is less than 15 mm.

3.4.8 Pipe Penetrations

Cutting structural members for passage of pipes or for pipe-hanger fastenings will not be permitted. Pipes that must penetrate concrete or masonry walls or concrete floors shall be core-drilled and provided with pipe sleeves. Each sleeve shall be Schedule 40 galvanized steel, ductile iron or cast iron pipe and shall extend through its respective wall or floor and be cut flush with each wall surface. Sleeves shall provide required clearance between the pipe and the sleeve per NFPA 13. The space between the sleeve and the pipe shall be firmly packed with mineral wool insulation. Where pipes penetrate fire walls, fire partitions, or floors, pipes shall be fire stopped in accordance with Section 07840 FIRESTOPPING. In penetrations that are not fire-rated or not a floor penetration, the space between the sleeve and the pipe shall be sealed at both ends with plastic waterproof cement that will dry to a firm but pliable mass or with a mechanically adjustable segmented elastomer seal.

3.4.9 Escutcheons

Escutcheons shall be provided for pipe penetration of ceilings and walls. Escutcheons shall be securely fastened to the pipe at surfaces through which piping passes.

3.4.10 Inspector's Test Connection

Unless otherwise indicated, test connection shall consist of 25 mm pipe connected to the remote branch line; a test valve located approximately 2 meters above the floor; a smooth bore brass outlet equivalent to the smallest orifice sprinkler used in the system; and a painted metal identification sign affixed to the valve with the words "Inspector's Test." The discharge orifice shall be located outside the building wall directed so as not to cause damage to adjacent construction or landscaping during full flow discharge.

3.4.11 Drains

Main drain piping shall be provided to discharge at a safe point outside the building. Auxiliary drains shall be provided as required by NFPA 13.

3.4.12 Identification Signs

Signs shall be affixed to each control valve, inspector test valve, main drain, auxiliary drain, test valve, and similar valves as appropriate or as required by NFPA 13. Hydraulic design data nameplates shall be permanently affixed to each sprinkler riser as specified in NFPA 13.

3.5 UNDERGROUND PIPING INSTALLATION

The fire protection water main shall be laid, and joints anchored, in accordance with NFPA 24. Minimum depth of cover shall be 1800 mm. The supply line shall terminate inside the building with a flanged piece, the bottom of which shall be set not less than 150 mm above the finished floor. A blind flange shall be installed temporarily on top of the flanged piece to prevent the entrance of foreign matter into the supply line. A concrete thrust block shall be provided at the elbow where the pipe turns up toward the floor. In addition, joints shall be anchored in accordance with NFPA 24 using pipe clamps and steel rods from the elbow to the flange above the floor and from the elbow to a pipe clamp in the horizontal run of pipe. Buried steel components shall be provided with a corrosion protective coating in accordance with AWWA C203. Piping more than 1500 mm outside the building walls shall meet the requirements of Section 02510 WATER DISTRIBUTION SYSTEM.

3.6 EARTHWORK

Earthwork shall be performed in accordance with applicable provisions of Section 02300 EARTHWORK.

3.7 ELECTRICAL WORK

Except as modified herein, electric equipment and wiring shall be in accordance with Section 16415 ELECTRICAL WORK, INTERIOR. Alarm signal wiring connected to the building fire alarm control system shall be in accordance with Section 13851 FIRE DETECTION AND ALARM SYSTEM, ADDRESSABLE. All wiring for supervisory and alarm circuits shall be #14 AWG solid copper installed in metallic tubing or conduit. Wiring color code shall remain uniform throughout the system.

3.8 PIPE COLOR CODE MARKING

Color code marking of piping shall be as specified in Section 09900 PAINTS AND COATINGS.

3.9 PRELIMINARY TESTS

The system, including the underground water mains, and the aboveground piping and system components, shall be tested to assure that equipment and components function as intended. The underground and aboveground interior piping systems and attached appurtenances subjected to system working pressure shall be tested in accordance with NFPA 13 and NFPA 24. Upon completion of specified tests, the Contractor shall complete certificates as specified in paragraph SUBMITTALS.

3.9.1 Underground Piping

3.9.1.1 Flushing

Underground piping shall be flushed in accordance with NFPA 24. This includes the requirement to flush the lead-in connection to the fire protection system at a flow rate not less than the calculated maximum water demand rate of the system.

3.9.1.2 Hydrostatic Testing

New underground piping shall be hydrostatically tested in accordance with NFPA 24. The allowable leakage shall be measured at the specified test pressure by pumping from a calibrated container. The amount of leakage at the joints shall not exceed 1.89 liters per hour per 100 gaskets or joints, regardless of pipe diameter.

3.9.2 Aboveground Piping

3.9.2.1 Hydrostatic Testing

Aboveground piping shall be hydrostatically tested in accordance with NFPA 13 at not less than 1400 kPa or 350 kPa in excess of maximum system operating pressure and shall maintain that pressure without loss for 2 hours. There shall be no drop in gauge pressure or visible leakage when the system is subjected to the hydrostatic test. The test pressure shall be read from a gauge located at the low elevation point of the system or portion being tested.

3.9.3 Testing of Alarm Devices

Each alarm switch shall be tested by flowing water through the inspector's test connection. Each water-operated alarm devices shall be tested to verify proper operation.

3.9.4 Main Drain Flow Test

Following flushing of the underground piping, a main drain test shall be made to verify the adequacy of the water supply. Static and residual pressures shall be recorded on the certificate specified in paragraph

SUBMITTALS. In addition, a main drain test shall be conducted each time after a main control valve is shut and opened.

3.10 FINAL ACCEPTANCE TEST

Final Acceptance Test shall begin only when the Preliminary Test Report has been approved. The Fire Protection Specialist shall conduct the Final Acceptance Test and shall provide a complete demonstration of the operation of the system. This shall include operation of control valves and flowing of inspector's test connections to verify operation of associated waterflow alarm switches. After operation of control valves has been completed, the main drain test shall be repeated to assure that control valves are in the open position. In addition, the representative shall have available copies of as-built drawings and certificates of tests previously conducted. The installation shall not be considered accepted until identified discrepancies have been corrected and test documentation is properly completed and received. The Contractor shall submit the Final Acceptance Test Report as specified in the Submittals paragraph.

3.11 ON-SITE TRAINING

The Fire Protection Specialist shall conduct a training course for operating and maintenance personnel as designated by the Contracting Officer. Training shall be provided for two 4-hour periods of normal working time and shall start after the system is functionally complete and after the Final Acceptance Test. Training sessions shall be coordinated with the Fort Drum Fire Department. The On-Site Training shall cover all of the items contained in the approved Operating and Maintenance Instructions.

-- End Of Section --"

2. Make the Following Changes to the drawings.

DRAWINGS

Revise the following Drawings as indicated. These Drawings are not being reissued at this time.

Drawing A-10

Change Note at Mechanical Room 107 to read:

"Insulated Metal Wall Panel R:20 (all sides), Roof Insulation R:40."

Drawing M-3

Add following Note to read:

"Contractor shall connect new water main to building to existing 65 DCW at a point above existing Mechanical Room slab. Contractor shall cut and repair existing Mechanical Room floor."

Drawing M-4

Add following Note to read:

“Contractor shall connect existing fire riser to new fire water line at a point above existing Mechanical Room slab. Contractor shall cut and repair existing Mechanical Room floor.”

Change Note 1 to read as follows:

1. Design of the system shall be based upon a water supply with a flow of 6,260 L/min at a residual pressure of 517 kPa and a flow of 7,383 L/min at a residual pressure of 317 kPa. Water supply shall be presumed available at the base of the riser.

Drawing M-6

Change Note 1 to read as follows:

1. Design of the system shall be based upon a water supply with a flow of 7,270 L/min at a residual pressure of 531 kPa and a flow of 8,708 L/min at a residual pressure of 338 kPa. Water supply shall be presumed available at the base of the rise

Drawing M-9

On the points list replace the note “25 sets of CO/NO2 monitors” with “15 sets of CO/NO2 monitors”. There are a total of 30 CO/ NO2 monitors.

(End of Summary of Changes)