

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT				1. CONTRACT ID CODE J		PAGE OF PAGES 1 5	
2. AMENDMENT/MODIFICATION NO. 0002		3. EFFECTIVE DATE 07-Aug-2003		4. REQUISITION/PURCHASE REQ. NO. W16ROE-3183-8070		5. PROJECT NO.(If applicable)	
6. ISSUED BY USA ENGINEER DISTRICT, NEW YORK ATTN: CENAN-CT ROOM 1843 26 FEDERAL PLAZA (DACW51) NEW YORK NY 10278-0090		CODE DACW51		7. ADMINISTERED BY (If other than item 6) See Item 6		CODE	
8. NAME AND ADDRESS OF CONTRACTOR (No., Street, County, State and Zip Code)				<input checked="" type="checkbox"/> X		9A. AMENDMENT OF SOLICITATION NO. DACW51-03-B-0015	
				<input checked="" type="checkbox"/> X		9B. DATED (SEE ITEM 11) 23-Jul-2003	
						10A. MOD. OF CONTRACT/ORDER NO.	
						10B. DATED (SEE ITEM 13)	
CODE		FACILITY CODE					
11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS							
<input checked="" type="checkbox"/> X The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offer <input type="checkbox"/> is extended, <input checked="" type="checkbox"/> X is not extended. Offer must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended by one of the following methods: (a) By completing Items 8 and 15, and returning <u>1</u> copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.							
12. ACCOUNTING AND APPROPRIATION DATA (If required)							
13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.							
A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.							
B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(B).							
C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:							
D. OTHER (Specify type of modification and authority)							
E. IMPORTANT: Contractor <input type="checkbox"/> is not, <input type="checkbox"/> is required to sign this document and return _____ copies to the issuing office.							
14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.) The purpose of this amendment is to make the following changes/clarifications to the solicitation Drawings and Specifications for Pompton Lake Dam, Flood Protection Project. Bid Opening Date remains 28 Aug 2003 2:00 P.M. Bidders must acknowledge receipt of this amendment by the date specified in the solicitation (or as amendment) by one of the following methods: By signing Block 15 below, by separate letter, or by telegram. FAILURE TO ACKNOWLEDGE AMENDMENTS BY THE DATE AND TIME SPECIFIED MAY RESULT IN REJECTIONS OF YOUR BID IN ACCORDANCE WITH THE LATE BID, LATE MODIFICATION OF BIDS, OR LATE WITHDRAWAL. All other terms and conditions remain the same.							
Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.							
15A. NAME AND TITLE OF SIGNER (Type or print)				16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)			
				TEL: EMAIL:			
15B. CONTRACTOR/OFFEROR _____ (Signature of person authorized to sign)		15C. DATE SIGNED		16B. UNITED STATES OF AMERICA BY _____ (Signature of Contracting Officer)		16C. DATE SIGNED 07-Aug-2003	

EXCEPTION TO SF 30
APPROVED BY OIRM 11-84

30-105-04

STANDARD FORM 30 (Rev. 10-83)
Prescribed by GSA
FAR (48 CFR) 53.243

SECTION SF 30 BLOCK 14 CONTINUATION PAGE

SUMMARY OF CHANGES

The following have been added by full text:

POMPTON LAKE DAM

Bid opening hour and date remain unchanged (28 August 2003 @ 02:00 P.M.).

1. The following changes shall be made to the specifications:

Specifications

1. Section 00700, Contract Clauses. Clauses 52.201-7000, 52.236-21, and 52.249-10 have been added.
2. Section 13073, Closed-Circuit Television (CCTV) System, has been deleted in its entirety and replaced with Section 16751A.
3. Section 16200, Instrumentation and Controls (SCADA), para. 2.2.18. Change Microprocessor quantity from "Pentium 4" to "Dual Pentium 4". Change Hard Disk quantity from "200 GB minimum with 11ms or less access time" to "2 - 200 GB minimum with 11ms or less access time".
4. Section 16200, Instrumentation and Controls (SCADA), para. 2.2.20. Add the following to the end of the last sub-paragraph:
"The system program/algorithm shall be programmable to allow for changes in pool elevation, stream flow, number/location of gauging stations utilized in the decision process. The software shall allow the expansion to add up to 12 additional gauge stations."
5. Section 16200, Instrumentation and Controls (SCADA), para. 3.14. Add the following to the end of the first sub-paragraph:
"The computer programming must be able to accept future modifications and changes in opening and closing frequencies of the gates."
6. Section 16751A, Add Section 16751A in its entirety as attached.

Drawings

1. Sheets F-7, F-8, F-9, F-10, and S-2 have been added.
2. This amendment shall be attached to the specifications and shall be a part thereof.

SECTION 00700 - CONTRACT CLAUSES

The following have been added by full text:

52.236-21 SPECIFICATIONS AND DRAWINGS FOR CONSTRUCTION (FEB 1997)

(a) The Contractor shall keep on the work site a copy of the drawings and specifications and shall at all times give the Contracting Officer access thereto. Anything mentioned in the specifications and not shown on the drawings, or shown on the drawings and not mentioned in the specifications, shall be of like effect as if shown or mentioned in both. In case of difference between drawings and specifications, the specifications shall govern. In case of discrepancy in the figures, in the drawings, or in the specifications, the matter shall be promptly submitted to the Contracting Officer, who shall promptly make a determination in writing. Any adjustment by the Contractor without such a determination shall be at its own risk and expense. The Contracting Officer shall furnish from time to time such detailed drawings and other information as considered necessary, unless otherwise provided.

(b) Wherever in the specifications or upon the drawings the words "directed", "required", "ordered", "designated", "prescribed", or words of like import are used, it shall be understood that the "direction", "requirement", "order", "designation", or "prescription", of the Contracting Officer is intended and similarly the words "approved", "acceptable", "satisfactory", or words of like import shall mean "approved by," or "acceptable to", or "satisfactory to" the Contracting Officer, unless otherwise expressly stated.

(c) Where "as shown," "as indicated", "as detailed", or words of similar import are used, it shall be understood that the reference is made to the drawings accompanying this contract unless stated otherwise. The word "provided" as used herein shall be understood to mean "provide complete in place," that is "furnished and installed".

(d) Shop drawings means drawings, submitted to the Government by the Contractor, subcontractor, or any lower tier subcontractor pursuant to a construction contract, showing in detail (1) the proposed fabrication and assembly of structural elements, and (2) the installation (i.e., fit, and attachment details) of materials or equipment. It includes drawings, diagrams, layouts, schematics, descriptive literature, illustrations, schedules, performance and test data, and similar materials furnished by the contractor to explain in detail specific portions of the work required by the contract. The Government may duplicate, use, and disclose in any manner and for any purpose shop drawings delivered under this contract.

(e) If this contract requires shop drawings, the Contractor shall coordinate all such drawings, and review them for accuracy, completeness, and compliance with contract requirements and shall indicate its approval thereon as evidence of such coordination and review. Shop drawings submitted to the Contracting Officer without evidence of the Contractor's approval may be returned for resubmission. The Contracting Officer will indicate an approval or disapproval of the shop drawings and if not approved as submitted shall indicate the Government's reasons therefor. Any work done before such approval shall be at the Contractor's risk. Approval by the Contracting Officer shall not relieve the Contractor from responsibility for any errors or omissions in such drawings, nor from responsibility for complying with the requirements of this contract, except with respect to variations described and approved in accordance with (f) below.

(f) If shop drawings show variations from the contract requirements, the Contractor shall describe such variations in writing, separate from the drawings, at the time of submission. If the Contracting Officer approves any such variation, the Contracting Officer shall issue an appropriate contract modification, except that, if the variation is minor or does not involve a change in price or in time of performance, a modification need not be issued.

(g) The Contractor shall submit to the Contracting Officer for approval four copies (unless otherwise indicated) of all shop drawings as called for under the various headings of these specifications. Three sets (unless otherwise indicated) of all shop drawings, will be retained by the Contracting Officer and one set will be returned to the Contractor.

(End of clause)

52.249-10 DEFAULT (FIXED-PRICE CONSTRUCTION) (APR 1984)

(a) If the Contractor refuses or fails to prosecute the work or any separable part, with the diligence that will insure its completion within the time specified in this contract including any extension, or fails to complete the work within

this time, the Government may, by written notice to the Contractor, terminate the right to proceed with the work (or the separable part of the work) that has been delayed. In this event, the Government may take over the work and complete it by contract or otherwise, and may take possession of and use any materials, appliances, and plant on the work site necessary for completing the work. The Contractor and its sureties shall be liable for any damage to the Government resulting from the Contractor's refusal or failure to complete the work within the specified time, whether or not the Contractor's right to proceed with the work is terminated. This liability includes any increased costs incurred by the Government in completing the work.

(b) The Contractor's right to proceed shall not be terminated nor the Contractor charged with damages under this clause, if--

(1) The delay in completing the work arises from unforeseeable causes beyond the control and without the fault or negligence of the Contractor. Examples of such causes include

(i) acts of God or of the public enemy,

(ii) acts of the Government in either its sovereign or contractual capacity,

(iii) acts of another Contractor in the performance of a contract with the Government,

(iv) fires,

(v) floods,

(vi) epidemics,

(vii) quarantine restrictions,

(viii) strikes,

(ix) freight embargoes,

(x) unusually severe weather, or delays of subcontractors or suppliers at any tier arising from unforeseeable causes beyond the control and without the fault or negligence of both the Contractor and the subcontractors or suppliers; and

(2) The Contractor, within 10 days from the beginning of any delay (unless extended by the Contracting Officer), notifies the Contracting Officer in writing of the causes of delay. The Contracting Officer shall ascertain the facts and the extent of delay. If, in the judgment of the Contracting Officer, the findings of fact warrant such action, the time for completing the work shall be extended. The findings of the Contracting Officer shall be final and conclusive on the parties, but subject to appeal under the Disputes clause.

(c) If, after termination of the Contractor's right to proceed, it is determined that the Contractor was not in default, or that the delay was excusable, the rights and obligations of the parties will be the same as if the termination had been issued for the convenience of the Government.

The rights and remedies of the Government in this clause are in addition to any other rights and remedies provided by law or under this contract.

(End of clause)

(a) "Definition. Contracting officer's representative" means an individual designated in accordance with subsection 201.602-2 of the Defense Federal Acquisition Regulation Supplement and authorized in writing by the contracting officer to perform specific technical or administrative functions.

(b) If the Contracting Officer designates a contracting officer's representative (COR), the Contractor will receive a copy of the written designation. It will specify the extent of the COR's authority to act on behalf of the contracting officer. The COR is not authorized to make any commitments or changes that will affect price, quality, quantity, delivery, or any other term or condition of the contract.

(End of clause)

(End of Summary of Changes)

CLOSED CIRCUIT TELEVISION SYSTEMS
08/00

1.1 REFERENCES

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

ELECTRONIC INDUSTRIES ALLIANCE (EIA)

EIA ANSI/TIA/EIA-568-B.2-1 (2002) Transmission Performance Specifications for 4-pair 100 ohm Category 6 Cabling

ICEA S-83-596 (1994) Fiber Optic Premises Distribution
Cable

IEEE Std 142 (1991) IEEE Recommended Practice for Grounding of Industrial and Commercial Power Systems

NEMA 250 (1997) Enclosures for Electrical Equipment
(1000 Volts Maximum)

NFPA 70 (1999) National Electrical Code

1.2.1 General

SECTION 16751A Page 1

1.2.2 System Overall Reliability Requirement

The system, including all components and appurtenances, shall be configured and installed to yield a mean time between failure (MTBF) of at least 10,000 hours, and shall be calculated based on the configuration specified in paragraph "System Overall Reliability Calculations."

1.2.3 Power Line Surge Protection

All equipment connected to AC power shall be protected from surges. Equipment protection shall withstand surge test waveforms described in IEEE C62.41. Fuses shall not be used for surge protection.

1.2.4 Video and Sync Signal Transmission Line Surge Protection

All cable, except fiber optic cable, used for sync or video signal transmission shall include protective devices to safeguard the CCTV equipment against surges. The surge suppression device shall not attenuate or reduce the video or sync signal under normal conditions. The surge suppression device shall be capable of dissipating not less than 1500 watts for 1 millisecond, and the response time from zero volts to clamping shall not be greater than 5 nanoseconds. Fuses shall not be used for surge protection.

1.2.5 Control Line Surge Protection

All cables and conductors, except fiber optic cables, which serve as communication, control, or signal lines shall be protected against surges and shall have surge protection installed at each end. Protection shall be furnished at the equipment and additional triple electrode gas surge protectors rated for the application on each wireline circuit shall be installed within 3 feet of the building cable entrance. Fuses shall not be used for surge protection. The inputs and outputs shall be tested in both normal mode and common mode using the following waveforms:

- a. A 10 microsecond rise time by 1000 microsecond pulse width waveform with a peak voltage of 1500 volts and a peak current of 60 amperes.
- b. An 8 microsecond rise time by 20 microsecond pulse width waveform with a peak voltage of 1000 volts and a peak current of 500 amperes.

1.2.6 Environmental Conditions

1.2.6.1 Field Equipment

The cameras and all other field equipment shall be rated for continuous operation under ambient environmental conditions of 14 degrees to 120 degrees F using no auxiliary heating or cooling equipment. Equipment shall be rated for continuous operation under the ambient environmental temperature, humidity, wind loading, ice loading, and vibration conditions specified or encountered for the installed location. Environmental enclosures shall be provided to house equipment not rated for the

environment. Environmental enclosures shall be such that equipment in the enclosure shall operate satisfactorily inside the enclosure.

1.2.7 Electrical Requirements

Equipment shall be able to tolerate variations in the voltage source of plus or minus 10 percent, and variations in the line frequency of plus or minus 2 percent with no degradation of performance.

1.2.8 Uninterruptible Power Supply (UPS)

The equipment power shall be supplied from the SCADA UPS.

1.3 DELIVERY OF TECHNICAL DATA AND COMPUTER SOFTWARE

All items of computer software and technical data (including technical data which relates to computer software), which are specifically identified in this specification shall be delivered strictly in accordance with the CONTRACT CLAUSES, SPECIAL CONTRACT REQUIREMENTS, Section 01330 SUBMITTAL PROCEDURES. All data delivered shall be identified by reference to the particular specification paragraph against which it is furnished.

1.3.1 Group I Technical Data Package

1.3.1.1 System Drawings

The data package shall include the following:

- a. System block diagram.
- b. CCTV system console installation, block diagrams, and wiring diagrams.
- b. Camera wiring and installation drawings.
- c. Interconnection with LAN system for video signal transmission system, block diagrams and wiring diagrams.
- d. Surge protection device installation.

1.3.1.2 Manufacturers' Data

The data package shall include manufacturers' data for all materials and equipment provided under this specification.

1.3.1.3 System Description and Analyses

The data package shall include complete system descriptions, analyses and calculations used in sizing the equipment required by these specifications. Descriptions and calculations shall show how the equipment will operate as a system to meet the performance of this specification. The data package shall include the following:

- a. Camera call-up response time.
- b. System start up and shutdown operations.

c. Manuals for CCTV equipment.

d. Data entry forms.

1.3.1.4 Software Data

The data package shall consist of descriptions of the operation and capability of system and application software as specified.

1.3.1.5 Overall System Reliability Calculations

The data package shall include all manufacturer's reliability data and calculations required to show compliance with the specified reliability. The calculations shall be based on all CCTV equipment associated with one camera circuit and the console CCTV equipment, excluding the data transmission media (DTM).

1.3.1.6 Certifications

All specified manufacturer's certifications shall be included with the data package.

1.3.2 Group II Technical Data Package

The Contractor shall verify that site conditions are in agreement with the design package. The Contractor shall submit a report to the Government documenting changes to the site, or conditions that affect performance of the system to be installed. For those changes or conditions which affect system installation or performance, provide (with the report) specification sheets, or written functional requirements to support the findings, and a cost estimate to correct the deficiency. The Contractor shall not correct any deficiency without written permission from the Government.

1.3.3 Group III Technical Data Package

The Contractor shall prepare test procedures and reports for the predelivery test. The Contractor shall deliver the predelivery test procedures to the Government for approval. After receipt by the Contractor of written approval of the predelivery test procedures, the Contractor may schedule the predelivery test. The final predelivery test report shall be delivered after completion of the predelivery test.

1.3.4 Group IV Technical Data Package

The Contractor shall prepare test procedures and reports for the performance verification test and the endurance test. The Contractor shall deliver the performance verification test and endurance test procedures to the Government for approval. After receipt by the Contractor of written approval of the test procedures, the Contractor may schedule the tests. The contractor shall provide a report detailing the results of the field test and a video tape as specified in paragraph "Contractor's Field Testing." The final performance verification and endurance test report shall be delivered after completion of the tests.

1.3.4.1 Operation and Maintenance Manuals

A draft copy of the operation and maintenance manuals, as specified for the Group V technical data package, shall be delivered to the Government prior to beginning the performance verification test for use during site testing.

1.3.4.2 Training Documentation

Lesson plans and training manuals for the training phases, including type of training to be provided with a sample training report, and a list of reference material, shall be delivered for approval.

1.3.4.3 Data Entry

The Contractor shall enter all data needed to make the system operational. The Contractor shall deliver the data to the Government on data entry forms, utilizing data from the contract documents, Contractor's field surveys, and all other pertinent information in the Contractor's possession required for complete installation of the data base. The Contractor shall identify and request from the Government, any additional data needed to provide a complete and operational CCTV system. The completed forms shall be delivered to the Government for review and approval at least 90 days prior to the Contractor's scheduled need date.

1.3.5 Group V Technical Data Package

Final copies of each of the manufacturer's commercial manuals arranged as specified bound in hardback, loose-leaf binders, shall be delivered to the Government within 30 days after completing the endurance test. The draft copy used during site testing shall be updated prior to final delivery of the manuals. Each manual's contents shall be identified on the cover. The manual shall include names, addresses, and telephone numbers of each subcontractor installing equipment and systems, and nearest service representatives for each item of equipment for each system. The manuals shall have a table of contents and tab sheets. Tab sheets shall be placed at the beginning of each chapter or section and at the beginning of each appendix. The final copies delivered after completion of the endurance test shall include all modifications made during installation, checkout, and acceptance.

1.3.5.1 Functional Design Manual

The functional design manual shall identify the operational requirements for the system and explain the theory of operation, design philosophy, and specific functions. A description of hardware and software functions, interfaces, and requirements shall be included for all system operating modes.

1.3.5.2 Hardware Manual

A manual shall describe all equipment furnished, including:

- a. General hardware description and specifications.

- b. Installation and checkout procedures.
- c. Equipment electrical schematics and layout drawings.
- d. System schematics and wiring lists.
- e. System setup procedures.
- f. Manufacturer's repair parts list indicating sources of supply.
- g. Interface definition.

1.3.5.3 Software Manual

The software manual shall describe the functions of all software, and shall include all other information necessary to enable proper loading, testing and operation, including:

- a. Definitions of terms and functions.
- b. Procedures for system boot-up.
- c. Description of using the programs.
- d. Description of required operational sequences.
- e. Directory of all disk files.
- f. Description of all communications protocols, including data formats, command characters, and a sample of each type of data transfer.

1.3.5.4 Operator's Manual

The operator's manual shall explain all procedures and instructions for operation of the system including:

- a. Cameras equipment.
- b. Use of the software.
- c. Operator commands.
- d. System start-up and shut-down procedures.
- e. Recovery and restart procedures.

1.3.5.5 Maintenance Manual

The maintenance manual shall describe maintenance for all equipment including inspection, periodic preventive maintenance, fault diagnosis, and repair or replacement of defective components.

1.3.5.6 As-Built Drawings

The Contractor shall maintain a separate set of drawings, elementary diagrams and wiring diagrams of the CCTV system to be used for as-built drawings. This set shall be accurately kept up to date by the Contractor with all changes and additions to the CCTV system and shall be delivered to the Government with the final endurance test report. In addition to being complete and accurate, this set of drawings shall be kept neat and shall not be used for installation purposes. Upon completion of the final system drawings, a representative of the Government will review the final system work with the Contractor. If the final system work is not complete, the Contractor will be so advised and shall complete the work as required. Final drawings submitted with the endurance test report shall be finished drawings on mylar or vellum, and as MicroStation files on CD-ROM. In addition to the requirement of this Section, As-Built Drawings shall be prepared and maintained by the contractor in accordance with Section 00800, SPECIAL CONTRACT REQUIREMENTS.

1.4 TESTING

1.4.1 General

The Contractor shall perform predelivery testing, site testing, and adjustment of the completed CCTV system. The Contractor shall provide all personnel, equipment, instrumentation, and supplies necessary to perform all testing. Written notification of planned testing shall be given to the Government at least 14 days prior to the test, and in no case shall notice be given until after the Contractor has received written approval of the specific test procedures.

1.4.2 Test Procedures and Reports

Test procedures shall explain, in detail, step-by-step actions and expected results demonstrating compliance with the requirements of the specification. Test reports shall be used to document results of the tests. Reports shall be delivered to the Government within 7 days after completion of each test.

1.5 TRAINING

1.5.1 General

The Contractor shall conduct training courses for designated personnel in the maintenance and operation of the CCTV system. The training shall be oriented to the specific system being installed under this contract. The trainer shall have 2 years experience in providing training on similar system. Training manuals shall be delivered for each trainee with two additional manuals delivered for archiving at the project site. The manuals shall include an agenda, defined objectives for each lesson, and a detailed description of the subject matter for each lesson. The Contractor is responsible for furnishing all audio-visual equipment and all other training materials and supplies. Where the Contractor presents portions of the

course through the use of audio-visual material, copies of the audio-visual materials shall be delivered to the Government, either as a part of the printed training manuals or on the same media as that used during the training sessions. Training shall consist of 4 hours operational and 4 hours maintenance instruction, including two 15-minute breaks and excluding lunchtime, Monday through Friday, during the daytime shift in effect at the facility. For guidance in planning the required instruction, the Contractor should assume the attendees will have a high school education or equivalent. Approval of the planned training schedule shall be obtained from the Government at least 30 days prior to the training. A maximum of 12 personnel will attend the course. No part of the training given during this course will be counted toward completion of the performance verification test. The course shall consist of classroom instruction, hands-on training, instruction on the specific hardware configuration of the installed system, and specific instructions for operating the installed system. The course shall demonstrate system start up, system operation, system shutdown, system recovery after a failure, the specific hardware configuration, and operation of the system and its software. The students should have no unanswered questions regarding operation of the installed CCTV system. The Contractor shall prepare and insert additional training material in the training manuals when the need for additional material becomes apparent during instruction. The Contractor shall prepare a written report after the completion of the course. The Contractor shall list in the report the times, dates, attendees and material covered at each training session. The Contractor shall describe the skill level of each student at the end of this course. The Contractor shall submit the report before the end of the performance verification test. The course shall include:

- a. General CCTV hardware, installed system architecture and configuration.
- b. Functional operation of the installed system and software.
- c. Operator commands.
- d. Fault diagnostics and correction.
- e. General system maintenance.
- f. Replacement of failed components and integration of replacement components into the operating CCTV system.

1.6 MAINTENANCE AND SERVICE

1.6.1 General Requirements

The Contractor shall provide all services required and equipment necessary to maintain the entire CCTV system in an operational state as specified for a period of 1 year after completion of the endurance test, and shall provide all necessary material required for the work. Impacts on facility operations shall be minimized when performing scheduled adjustments or other unscheduled work.

1.6.2 Description of Work

The adjustment and repair of the CCTV system includes all computer equipment, software updates, and signal transmission equipment. Provide the manufacturer's required adjustments and all other work necessary.

1.6.3 Personnel

Service personnel shall be qualified to accomplish all work promptly and satisfactorily. The Government shall be advised in writing of the name of the designated service representative, and of any changes in personnel.

1.6.4 Records and Logs

The Contractor shall keep records and logs of each task, and shall organize cumulative records for each major component, and for the complete system chronologically. A continuous log shall be maintained for all devices. The log shall contain calibration, repair, and programming data. Complete logs shall be kept and shall be available for inspection on site, demonstrating that planned and systematic adjustments and repairs have been accomplished for the CCTV system.

1.6.5 Work Requests

The Contractor shall separately record each service call request, as received. The form shall include the serial number identifying the component involved, its location, date and time the call was received, nature of trouble, names of the service personnel assigned to the task, instructions describing what has to be done, the amount and nature of the materials to be used, the time and date work started, and the time and date of completion. The Contractor shall deliver a record of the work performed within 5 days after work is completed.

1.6.6 System Modifications

The Contractor shall make any recommendations for system modification in writing to the Government. No system modifications, including operating parameters and control settings, shall be made without prior approval of the Government. Any modifications made to the systems shall be incorporated into the operations and maintenance manuals, and other documentation affected.

1.6.7 Software

The Contractor shall recommend all software updates to the Government for approval. Upon Government approval, updates shall be accomplished in a timely manner, fully coordinated with the CCTV system operators, operation in the system verified, and shall be incorporated into the operations and maintenance manuals, and software documentation. There shall be at least one scheduled update near the end of the first year's warranty period, at which time the Contractor shall install and validate the latest released version of the manufacturer's software.

PART 2 PRODUCTS

2.1 MATERIALS AND EQUIPMENT

All system hardware and software components shall be produced by manufacturers regularly engaged in the production of CCTV equipment and software. Units of the same type of equipment shall be products of a single manufacturer. All material and equipment shall be new and currently in production. Each major component of equipment shall have the manufacturer's name and address, and the model and serial number in a conspicuous place. Both Television and Computing devices shall comply with 47 CFR 15, Subpart B.

2.1.2 Soldering

All soldering shall be done in accordance with standard industry practices.

2.2 ENCLOSURES

The Contractor shall provide metallic enclosures as needed for equipment not housed in racks or supplied with a housing. The enclosures shall be as specified or shown.

2.2.1 Exposed-to-Weather

Enclosures to house equipment in an outdoor environment shall meet the requirements of NEMA 250 Type 4X.

2.3 TAMPER PROVISIONS

Enclosures, cabinets, housings (other than environmental camera housings), boxes, raceways, conduits, and fittings of every description having hinged doors or removable covers, and which contain any part of the CCTV equipment or power supplies, shall be provided with cover operated, corrosion-resistant tamper switches, arranged to initiate an alarm signal when the door or cover is moved. Tamper switches shall be mechanically mounted to maximize the defeat time when enclosure covers are opened or removed. The enclosure and the tamper switch shall function together to not allow direct line of sight to any internal components and tampering with the switch or the circuits before the switch activates. Tamper switches shall be inaccessible until the switch is activated; have mounting hardware concealed so that the location of the switch cannot be observed from the exterior of the enclosure; be connected to circuits which are under electrical supervision at all times, irrespective of the protection mode in which the circuit is operating; shall be spring-loaded and held in the closed position by the door cover; and shall be wired so that they break the circuit when the door or cover is disturbed. Tamper switches on the doors which must be opened to make routine maintenance adjustments to the system and to service the power supplies shall be push/pull-set, automatic reset type.

2.3.1 Enclosure Covers

Covers of pull and junction boxes provided to facilitate installation of the system need not be provided with tamper switches if they contain no splices or connections, but shall be protected by tack welding or brazing the covers in place. Zinc labels shall be affixed to such boxes indicating they contain no connections.

2.3.2 Conduit-Enclosure Connections

All conduit-enclosure connections shall be protected by tack welding or brazing the conduit to the enclosure. Tack welding or brazing shall be done in addition to standard conduit-enclosure connection methods as described in NFPA 70.

2.4 LOCKS AND KEY-LOCK OPERATED SWITCHES

2.4.1 Locks

Locks shall be provided on system enclosures for maintenance purposes shall be [UL listed, round-key type, with three dual, one mushroom, and three plain pin tumblers] [or] [conventional key type lock having a combination of five cylinder pin and five-point three position side bar]. Keys shall be stamped "U.S. GOVT. DO NOT DUP." The locks shall be so arranged that the key can only be withdrawn when in the locked position. All maintenance locks shall be keyed alike and only two keys shall be furnished for all of these locks.

2.4.2 Key-Lock-Operated Switches

All key-lock-operated switches required to be installed on system components shall be UL listed, [with three dual, one mushroom, and three plain pin tumblers,] [or] [conventional key type lock having a combination of five cylinder pin and five-point three position side bar]. Keys shall be stamped "U.S. GOVT. DO NOT DUP." Key-lock-operated switches shall be two position, with the key removable in either position. All key-lock-operated switches shall be keyed differently and only two keys shall be furnished for each key-lock-operated-switch.

2.5 SYSTEM INTEGRATION

Equipment shall be supplied with all adapters, terminators, cables, main frames, card cages, power supplies, rack mounts, and appurtenances as needed.

2.6 SOLID STATE CAMERAS

The scene from each camera shall appear clear, crisp, and stable on the respective monitor during both daytime and nighttime operation. Component equipment shall minimize both preventive and corrective maintenance. Components shall be compatible with other components and with system as a whole and shall, to the greatest extent possible, be supplied by the same manufacturer. The system shall utilize standard Internet TCP/IP suite of protocols and operates on MicroSoft Windows 2000 operating system.

2.6.1 IR Low Light Color IP Camera

- a. Except as specified herein, CCTV camera shall:
 - (1) Consist of support structure, base plate, lens plate, image sensor, and printed circuit boards with electronic components;
 - (2) Be identified with the manufacturer's part number, model number, lens installed, and a serial number;
 - (3) Operate over a voltage range of 9-15V AC, min 10VA ac at 60 Hz;

- (4) Operating Conditions: - Temp: 41-122o F, Humidity: 8-80% RHG.
- (5) Approvals EMC - The equipment must comply with the requirements in 47 CFR 15, Subpart B of FCC Rules for Class A computing devices.
- (6) Have electronic circuits which use solid-state devices and a 1/3 inch solid-state imaging device;
- (7) Be constructed to provide rigid support for electrical and optical systems so that unintentional changes in alignment or microphonic effects will not occur during operation, movement, or lens adjustments;
- (8) Networking - 10baseT Ethernet or 100baseTX Fast Ethernet, TCP/IP, HTTP, FTP, SMTP, NTP, ARP and BOOTP. The camera shall connect to the network via fiber optic cable. Category 5 to fiber optic conversion modules shall be acceptable, provided the system is reliable and stable.
- (9) I/O-Connector - One RS-485/422 port for connecting PTZ devices, etc.
- (10) Lens - Automatic DC Iris lens with CS Mount, manual zoom, variable focus, and exposure control. Variable shutter speeds between 1/50 - 1/10000 (PAL) and 1/60 -1/10000 (NTSC).
- (11) Electronic Shutter - Full DC-iris support and variable shutter speeds 1/50-1/10000 (PAL) and 1/60-1/10000 (NTSC).
- (12) Compression and Performance - Motion-JPEG images at up to 25/30 (PAL/NTSC) images per second, as well as single JPEG images that feature user-controlled compression levels.
- (13) Sensitivity: Illumination - 1 to 20000 Lux, with F1.0 DC-Iris lens.

2.6.2 Connectors

Cameras lens shall have auto iris functions and be supplied with connectors and wiring as needed to operate the lens functions.

2.6.3 Camera Power Supply

Provide a power supply to power all IP Cameras from a single 120 V ac power source. The camera power supply shall be powered from the SDCADA UPS. The supply shall provide power for all camera equipment, including power for the auto iris function.

2.7 CAMERA LENSES

Camera lenses shall be all glass with coated optics. The lens mount shall be a CS mount, compatible with the cameras selected. The lens shall be supplied with the camera, and shall have a maximum f-stop opening of f/1.2 or the maximum available for the focal length specified. The lens shall be equipped with an auto-iris mechanism unless otherwise specified. Lenses having auto iris shall be supplied with connectors, wiring, receiver/drivers, and controls as needed to operate the lens functions. Lenses shall have sufficient circle of illumination to cover the image sensor evenly. Lenses shall not be used on a camera with an image format larger than the lens is designed to cover. Lens focal lengths shall be these specified in the manufacturer's lens selection tables.

2.8 CAMERA HOUSINGS AND MOUNTS

The camera and lens shall be enclosed in a tamper resistant housing as specified below. Any ancillary housing mounting hardware needed to install the housing at the camera location shall be provided as part of the housing. The camera and lens contained in a camera housing shall be installed on a camera support as shown. Any ancillary mounting hardware needed to install the support and to install the camera on the support shall be provided as part of the support. The camera support shall be capable of supporting the equipment to be mounted on it including wind and ice loading normally encountered at the site.

2.8.1 Environmentally Sealed Camera Housing

The housing shall be designed to provide a condensation free environment for camera operation. The housing shall be constructed to be dust and water tight, and fully operational in 100 percent condensing humidity. The housing shall be purged of atmospheric air and pressurized with dry nitrogen, shall be equipped with a fill valve, overpressure valve, and shall have a humidity indicator visible from the exterior. Housing shall not have a leak rate greater than 2 pounds per square inch at sea level within a 90 day period. The housing shall be equipped with supplementary camera mounting blocks or supports as needed to position the specified camera and lens to maintain the proper optical centerline. All electrical and signal connections required for operation of the camera and lens shall be supplied. The housing shall provide the environment needed for camera operation, and shall keep the viewing window free of fog, snow, and ice. The housing shall be equipped with a sunshield, and both the housing and the sunshield shall be white. A mounting bracket which can be adjusted to center the weight of the housing and camera assembly shall be provided as part of the housing.

2.8.2 Exterior Wall Mount

The exterior camera wall mount shall be 16 inches long, and shall have an adjustable head for mounting the camera. The wall mount and head shall be constructed of aluminum, stainless steel, or steel with a corrosion-resistant finish. The head shall be adjustable for not less than plus and minus 90 degrees of pan, and not less than plus and minus 45 degrees of tilt.

2.9 WIRE AND CABLE

The Contractor shall provide all wire and cable not indicated as Government Furnished Equipment. All wire and cable components shall be able to withstand the environment the wire or cable is installed in for a minimum of 20 years.

2.9.1 Low Voltage Control Wiring

Twisted pair low voltage control wiring to be used above ground or in conduit shall be provided as described in Section 16415 ELECTRICAL WORK, INTERIOR.

2.9.3 LAN Interconnection Wiring

Horizontal cable shall meet the requirements of EIA ANSI/TIA/EIA-568-B.2-1 for Category 5. Cable shall be label-verified. Cable jacket shall be

factory marked at regular intervals indicating verifying organization and performance level. Cable shall be rated CMG or as appropriate, per NFPA 70.

2.9.4 Fiber Optic Multimode Cable

Multimode fiber optic backbone cable shall meet the requirements of EIA ANSI/TIA/EIA-568-B and ICEA S-83-596 for 62.5/125 micrometer multimode graded index optical fiber cable. Numerical aperture for each fiber shall be a minimum of 0.275. Cable construction shall be tight buffered type. Individual fibers shall be color coded for identification. Cable shall be imprinted with fiber count and aggregate length at regular intervals. Cable shall be rated OFNG per NFPA 70.

2.10 DISPLAY SOFTWARE

2.10.1 Software Performance Requirements

Provide software in modules to meet application requirements of this section. Software shall include the operating system (OS), be complete off-the-shelf, modifiable for specific CCTV application specified herein, and be a product of and supported by the CCTV central processor manufacturer. Software shall be menu-driven. Software provided shall be documented in a user's manual which shall be approved by the Government prior to system implementation.

The Display Soft shall provide the following features:

- a. Captures high-quality motion JPEG images at up to 30 FPS
- b. Variable image resolution and compression options depending on application
- c. Total scalability for an unlimited number of cameras
- d. Monitor, record, and view images from anywhere on the network or Internet
- e. Store images at variable frame rates or on motion detection to reduce storage requirements
- f. Integrates with CCTV security and facility management applications
- g. User-friendly graphical interface and online help for ease of use
- h. Single point control of all cameras on the network including setup and maintenance.
- i. Video recording capabilities:
 - 1) Records video images on local or remote hard drives.
 - 2) Variable recording rates
 - 3) Motion detection with user selected regions of video
- j. Video conversion capabilities
 - 1) Convert recorded video images to AVI movie format for playback with Windows Media Player or QuickTime
 - 2) Variable frame rate and image size
 - 3) Image optimization
- k. Video viewing capabilities
 - 1) Any number of users can view live images from anywhere on the network, or remotely over the Internet.
 - 2) Multiple screen views
 - 3) Control Pan/Tilt/Zoom cameras
 - 4) Instant record & playback
- l. Archive playback capabilities

- 1) View recorded images, from anywhere on the network, with easy to use controls.
 - 2) Quick access to recorded images by date and time
 - 3) Print or export a defined range of images
- m. Advanced scheduling capabilities
- 1) Schedule recording times for any time of the day or week with the built-in scheduler
 - 2) Schedule recording on any camera down to 15-minute increments
 - 3) Schedule continuous storage or on motion detection

A known source for software meeting the above requirements is:

SharksEye Systems Inc
 5060 Key Largo Drive
 Punta Gorda, FL 33950
 Tel. 877 912 6192
 Fax 941 639 7494

Other software suppliers shall be considered provided the software meets all of the above requirements.

2.10.3 Camera Support Software

Support software shall consist of software implemented to support system operation, such as camera system setup and off-line maintenance routines.

2.7 LAN HUB

Provide new LAN hubs at the spillway and at North Jersey District Water Supply Commission Headquarters at Wanaque Dam.

The LAN hub shall provide high-speed LAN connections for all equipment, IP cameras, SCADA computer equipment and the high-speed network connections. The LAN hub shall provide 24 auto-sensing ports, which automatically detect the speed of the attached device and optimize network performance at either 10 Mbps or 100 Mbps.

Interface Type:	Cable (Category 5)
Operating System Compatibility:	PC
Networking Type:	Hub
Networking Connection Type:	Ethernet (10/100Base-T)
	Fast Ethernet (100Base-T)
Network Ports:	24 Ports
Data Transfer Rate:	100 Mbps

PART 3 EXECUTION

3.1 INSTALLATION

The Contractor shall install all system components including Government furnished equipment, and appurtenances in accordance with the manufacturer's instructions, and as shown, and shall furnish all necessary connectors, terminators, interconnections, services, and adjustments required for a complete and operable system. Raceways shall be furnished and installed as specified in Section 16415 ELECTRICAL WORK, INTERIOR. DTM shall not be pulled into conduits or placed in raceways, compartments, outlet boxes,

junction boxes, or similar fittings with other wiring. All other electrical work shall be as specified in the above sections including grounding to preclude ground loops, noise, and surges from adversely affecting system operation.

3.1.1 Current Site Conditions

The Contractor shall visit the site and verify that site conditions are in agreement with the design package. The Contractor shall report all changes to the site or conditions that will affect performance of the system to the Government in a report as defined in paragraph Group II Technical Data Package. The Contractor shall not take any corrective action without written permission from the Government.

3.1.3 Enclosure Penetrations

All enclosure penetrations shall be from the bottom unless the system design requires penetrations from other directions. Penetrations of interior enclosures involving transitions of conduit from interior to exterior, and all penetrations on exterior enclosures shall be sealed with rubber silicone sealant to preclude the entry of water. The conduit riser shall terminate in a hot-dipped galvanized metal cable terminator. The terminator shall be filled with an approved sealant as recommended by the cable manufacturer, and in such a manner that the cable is not damaged.

3.1.4 Cold Galvanizing

All field welds and brazing on factory galvanized boxes, enclosures, and conduits shall be coated with a cold galvanized paint containing at least 95 percent zinc by weight.

3.1.5 Cameras

The Contractor shall install the cameras with the proper focal length lens as indicated for each zone; connect power and signal lines to the camera; set cameras with fixed iris lenses to the proper f-stop to give full video level; aim camera to give field of view as needed to cover the alarm zone; aim fixed mount cameras installed outdoors facing the rising or setting sun sufficiently below the horizon to preclude the camera looking directly at the sun; focus the lens to give a sharp picture over the entire field of view; and synchronize all cameras so the picture does not roll on the monitor when cameras are selected. Dome cameras shall have all preset positions defined and installed.

3.1.6 Video Signal Equipment

The Contractor shall install the video signal equipment as specified by the manufacturer and as shown; connect video or signal inputs and outputs as shown and specified; terminate video inputs as required; connect alarm signal inputs and outputs as required; connect control signal inputs and outputs as required; and connect electrically powered equipment to AC power.

3.1.7 Camera Housings, Mounts, and Poles

The Contractor shall install the camera housings and mounts as specified by the manufacturer and as shown, provide mounting hardware sized appropriately to secure each camera, housing and mount with maximum wind and ice loading encountered at the site; provide a foundation for each camera pole as specified and shown; provide a ground rod for each camera pole and connect the camera pole to the ground rod as specified in Section 16415 ELECTRICAL WORK, INTERIOR; provide electrical.

3.2 SYSTEM STARTUP

The Contractor shall not apply power to the CCTV system until the following items have been completed:

- a. CCTV system equipment items and DTM have been set up in accordance with manufacturer's instructions.
- b. A visual inspection of the CCTV system has been conducted to ensure that defective equipment items have not been installed and that there are no loose connections.
- c. System wiring has been tested and verified as correctly connected as indicated.
- d. All system grounding and transient protection systems have been verified as properly installed and connected as indicated.
- e. Power supplies to be connected to the CCTV system have been verified as the correct voltage, phasing, and frequency as indicated.
- f. Satisfaction of the above requirements shall not relieve the Contractor of responsibility for incorrect installation, defective equipment items, or collateral damage as a result of Contractor work/equipment.

3.3 SITE TESTING

3.3.1 General

The Contractor shall provide all personnel, equipment, instrumentation, and supplies necessary to perform all site testing. The Government will witness all performance verification testing. Written permission shall be obtained from the Government before proceeding with the next phase of testing. Original copies of all data produced during performance verification testing shall be turned over to the Government at the conclusion of each phase of testing prior to Government approval of the test.

3.3.2 Contractor's Field Testing

The Contractor shall calibrate and test all equipment, verify DTM operation, place the integrated system in service, and test the integrated system. Ground rods installed by the Contractor shall be tested as specified in IEEE Std 142. The Contractor shall deliver a report describing results of functional tests, diagnostics, and calibrations including written certification to the Government that the installed complete system has been calibrated, tested, and is ready to begin performance verification testing. The report shall also include a copy of the approved performance

verification test procedure. In addition, the Contractor shall make a master video tape recording showing typical day and night views of each camera in the system and shall deliver the tape with the report. Note any objects in the field of view that might produce highlights that could cause camera blinding. Note any objects in the field of view or anomalies in the terrain which may cause blind spots. Note if a camera cannot be aimed to cover the zone and exclude the rising or setting sun from the picture. Note night assessment capabilities and whether lights or vehicle headlights cause blooming or picture degradation. If any of the above conditions or other conditions exist that cause picture degradation or interfere with the camera field of view, the Contractor shall inform the Contracting Officer. The tape shall be recorded using the video recorder installed as part of the CCTV system. If a recorder is not part of the CCTV system, the Contractor shall provide the tape in Video Home System (VHS) format. The Contractor shall provide the Government with the original tape as part of the documentation of the system and shall submit a letter certifying that the CCTV system is ready for performance verification testing. The field testing shall as a minimum include:

- a. Verification that the video transmission system and any signal or control cabling have been installed, tested, and approved as specified.
- b. Verification that software is functioning correctly. All software functions shall be exercised.
- d. Verification that all video sources and video outputs provide a full bandwidth signal that complies with EIA 170 at all video inputs.
- e. Verification that all video signals are terminated properly.
- f. Verification that all cameras are aimed and focused properly. The Contractor shall conduct a walk test of the area covered by each camera to verify the field of view.
- g. Verification that cameras facing the direction of rising or setting sun are aimed sufficiently below the horizon so that the camera does not view the sun directly.
- h. If vehicles are used in proximity of the assessment areas, verification of night assessment capabilities and determination if headlights cause blooming or picture degradation.
- i. Verification that all cameras are synchronized and that the picture does not roll when cameras are switched.

The Contractor shall deliver a report describing results of functional tests, diagnostics, and calibrations including written certification to the Government that the installed complete system has been calibrated, tested, and is ready to begin performance verification testing. The report shall also include a copy of the approved performance verification test procedure.

3.3.3 Performance Verification Test

The Contractor shall demonstrate that the completed CCTV system complies with the contract requirements. Using approved test procedures, all physical and functional requirements of the project shall be demonstrated and shown. The performance verification test, as specified, shall not be started until receipt by the Contractor of written permission from the Government, based on the Contractor's written report. This shall include certification of successful completion of Contractor Field Testing as specified in paragraph "Contractor's Field Testing," and upon successful completion of training as specified. The Government may terminate testing at any time when the system fails to perform as specified. Upon successful completion of the performance verification test, the Contractor shall deliver test reports and other documentation as specified to the Government.

-- End of Section --